

GLARE[®] and Bonded Repairs Friday May 11th 2007

Agenda

- What is GLARE[®]?
 - GLARE[®] characteristics.
 - GLARE[®] damage behaviour.
- Present repairs, riveted.
- Future repairs, bonded.
 - How to perform repair
 - Testing of repairs
- GLARE[®] repairs patches
- General developments






What is **GLARE[®]**?



 GLARE is a hybrid material built-up from alternating layers of aluminium and glass fibre reinforced metal adhesive



STORK

GLARE[®] build up.

- GLARE[®] build-up:
 - Aluminium layer thickness: 0.2 0.3 0.4 0.5 mm
 - Fibre/adhesive layer build-up from multiple 0.125 mm UD layers
 - FM94 epoxy adhesive for structural metal bonding
- Standard grades:

	Fibre/adhesive layer thickness	Fibre/adhesive laver build-up
GLARE 2A	0.25 mm	layer build-up 0°/0°
GLARE 2B	0.25 mm	90°/90°
GLARE 3	0.25 mm	0°/90°
GLARE 4A	0.375 mm	0°/90°/0°
GLARE 4B	0.375 mm	90°/0°/90°
GLARE 5	0.5 mm	0°/90°/90°/0°

Example: GLARE 4B-4/3-0.4
 0.4 mm thick aluminium layers
 4 aluminium layers, 3 fibre/adhesive layers



GLARE[®] characteristics.

- Static strength properties
 - Design values for GLARE[®] in 4/3-0.4 lay-up (MPa):


	2024-T3	GLARE 2	GLARE 3	GLARE 4
Tensile ult. L	440	910	625	795
Tensile ult. LT	435	300	610	525
Tensile yield L	325	325	285	290
Tensile yield LT	290	215	260	230
Compr. yield L	270	305	260	
Compr. yield LT	310	230	270	
Bearing ult.	890	680	760	630
Blunt notch L*	410	600	425	510
Blunt notch LT*	400	190	415	360
E-modulus L	72400	66500	59500	59000
G-modulus	27600	20500	20500	18700
*:typical values				



GLARE[®] characteristics. (cont'd)

- Mix of composite and metal properties/behaviour, GLARE[®] offers:
 - Static strength
 (topsile compression
 - (tensile, compression, etc)
 - Damage Tolerance
 - Excellent Fatigue behaviour
 - Impact resistance
 - Residual strength
- Properties can be tailored:
 - Thicker or thinner aluminium layers
 - More or fewer fibre/adhesive layers
 - fibre adhesive layers at specific angles (e.g. ±45°)

- Corrosion resistance
- Lightning strike resistance
- Fire resistance
- Easy workshop handling
- Easy reparability





GLARE[®] damage behaviour

- FOD causes a dent (impact) or a scratch, similar to aluminium
- Inspectability of FOD similar to aluminium
- Penetration energy higher than for aluminium and composites
- Debonding sizes resulting from impact are small compared to the dent size
- Effect of FOD on compression properties similar to aluminium
- GLARE exhibits slow fatigue crack growth and high residual strength in the presence of FOD


Present repairs, riveted.

- Repairability
 - The same repair methods can be applied as for aluminium
 - Superficial damage (corrosion, scratches) can be worked out
 - Riveted or bonded patches can be applied
 - Good fatigue and damage tolerance performance of repaired structure














Friday May 11th 2007

Proprietary Stork Fokker Information



Present repairs, riveted. (cont'd)




Proprietary Stork Fokker Information




Q

Future repairs, bonded.

- Advantages:
 - Fatigue insensitive
 - Corrosion
 - Lower design weight, reduced skin thickness





 $StandGL_bondrun_out_STATUS.pdf$

Proprietary Stork Fokker Information




How to perform bonded repair

- Standard (SRM) procedures.
- No special tools or equipment.
- 1st aim hot bonded adhesive, later cold bonded



Cleaning of bonding surface



Bonding film cut to shape




Application of vacuum foil, thereafter start of curing with Heatcom[®] device, low vacuum pressure

Proprietary Stork Fokker Information

STORIA

Testing of bonded repairs



Megaliner barrel bonded repairs

Three outdoor exposure + CA fatigue tests

Proprietary Stork Fokker Information

STORIS

on both sides of panel. 2024T3, t=0.6mm, w=50mm

Testing of bonded repairs (cont'd)

- The tests are still ongoing:
 - No problem to bond a repair (GLARE-)patch to GLARE®
 - Fine tuning of repair patch
 - Feasibility of standard GLARE patch.
 - Outdoor exposure program to be completed. Preliminary results (after 2 years outdoor exposure): no effect of outdoor exposure (Me/Me bonding is not affected)





GLARE[®] repairs patches

US Air Force/Lockheed Martin C-5A Galaxy: Bonded Patch Repairs

- Material: Two GLARE 2-3/2-0.2 repairs installed October 1995
- Design: Patch bonded over a fuselage longitudinal butt-joint with AF 163-2M
- Due to the poor fatigue performance of the aluminium 7079-T6 skin, significant fatigue damage did occur. When riveted aluminium patches were used, new cracks typically nucleate in the skin at the corners of the patches, leading to ever larger repairs.
- Status:
 - No skin crack extension
 - No debonding
 - No damage to GLARE patch





GLARE[®] repairs patches (cont'd)

- Status:
 - No skin crack extension
 - No debonding
 - No damage to GLARE patch





Proprietary Stork Fokker Information



General developments

- Integrated systems, e.g.:
 - De-icing system leading edge nose skin
 - No bleed air required (energy decrease)
 - Full electrical aircraft (weight decrease)
- Friction stir welding to eliminate splices. (with 2024 GLARE)
- Improving GLARE properties (and Fibre Metal Laminates)
 - Higher static properties: to be achieved by higher strength alloys
 - Lower density due to lower density aluminium alloys (e.g. Al/Li)
 - Increase stiffness: to be achieved by higher stiffness fibres
- Automation of pretreatment (continue process), lay up and inspection (US).
- Larger Skin panels \rightarrow



General developments (cont'd)

- Larger panels:
 - Easier Assembly
 - Less joints





Dimensions: 3.5 x 11 meters (10x33ft)

STORI4

Proprietary Stork Fokker Information

STORK[®] knows-how

Copyright protection note

All rights reserved. Disclosure to third parties of this document or any part thereof, or the use of any information contained therein for purpose other than provided for by thisdocument, is not permitted, except with prior and expresswritten permission.

STORIA

Proprietary Stork Fokker Information

STORIC


Stork Fokker AESP B.V.


FAA / CACRC / NIAR

Crack Propagation is no Sizing Parameter

General differences of GLARE® compared with Aluminium:

- Fatigue life is longer
- Crack initiation is earlier
- Contribution of crack propagation period on total fatigue life is larger





Airbus Costumer Benefit from Fiber Metal Laminates - ESAS - Ref. L53PR0605135 - Issue 1

May 2006 Page 8



STORIS


20

Proprietary Stork Fokker Information

Stork Fokker AESP B.V.

FAA / CACRC / NIAR

GLARE[®] Design Features – "Giant" Tool Box



Proprietary Stork Fokker Information



Fire resistance

- GLARE shows excellent fire resistance behaviour
 - fire wall tests: 15 minutes minimum at 1100°C
 - No flame penetration
 - Exposed aluminium layer melts
 - Epoxy around glass fibres carbonizes and protect remaining aluminium layers.
 - Backside temperature reduced by more than half due to isolating effect of delaminated glass fibre layers



